

Bilance zemin - Revitalizační opatření v povodí Velmovického potoka v k.ú. Mašovice

SO objekt	Hloubení jam, rýh (m ³)	Sejmutí ornice (m ²)	Sejmutí ornice m ² x 0,2 m = (m ³)	Sejmutí drnu (m ²)	Sejmutí drnu m ² x 0,1 m = (m ³)	Celkem (m ³)
SO 01	2795,597	2737,000	547,400	572,000	57,200	3400,197
SO 02	591,098	818,000	163,600	325,000	32,500	787,198
SO 03	210,082	25,000	5,000	105,000	10,500	225,582
SO 04	72,260	0,000	0,000	100,000	10,000	82,260
SO 05	0,000	0,000	0,000	0,000	0,000	0,000
SO 06	71,286	117,000	23,400	0,000	0,000	94,686
SO 07	434,826	1248,000	249,600	0,000	0,000	684,426
SO 08	301,863	689,000	137,800	0,000	0,000	439,663
SO 09	1956,358	4207,000	841,400	0,000	0,000	2797,758
SO 10	2395,707	1121,000	224,200	0,000	0,000	2619,907
SO 11	419,948	120,000	24,000	0,000	0,000	443,948
SO 12	25,785	27,000	5,400	0,000	0,000	31,185
SO 13	23,232	17,000	3,400	0,000	0,000	26,632
SO 14	0,000	0,000	0,000	0,000	0,000	0,000
SO 15	0,000	0,000	0,000	0,000	0,000	0,000
Celkem	9298,042		2225,200		110,200	11633,442

SO objekt	Zásyp jam, rýh (m ³)	Rozprostrání ornice (m ²)	Rozprostření ornice m ² x 0,1 m = (m ³)	Zemina do hráze (m ³)	Celkem (m ³)	KONTROLA Přesun na skládku (m ³)
SO 01	0,000	373,940	37,394	0,000	37,394	2282,753
SO 02	0,000	658,532	65,853	1764,823	1830,676	0,000
SO 03	0,000	0,000	0,000	262,154	262,154	0,000
SO 04	0,000	0,000	0,000	0,000	0,000	82,260
SO 05	0,000	0,000	0,000	0,000	0,000	0,000
SO 06	0,000	0,000	0,000	0,000	0,000	94,686
SO 07	0,000	0,000	0,000	60,138	60,138	624,288
SO 08	0,000	0,000	0,000	68,199	68,199	371,464
SO 09	0,000	204,860	20,486	0,000	20,486	1817,386
SO 10	0,000	1187,000	118,700	3461,093	3579,793	0,000
SO 11	0,000	0,000	0,000	335,126	335,126	108,822
SO 12	0,000	0,000	0,000	0,000	0,000	31,185
SO 13	2,312	4,855	0,486	0,000	2,798	23,834
SO 14	0,000	0,000	0,000	0,000	0,000	0,000
SO 15	0,000	0,000	0,000	0,000	0,000	0,000
Celkem	2,312		242,919	5951,533	6196,764	5436,678

Veškeré výkopy a odstranění ornice a drnu - zásypy, násypy a ornice =
Na skládku bude uloženo 5437 m³

5436,678 m³